



**TORFICHEN
WIND FARM**

FIGURE 3.15

**TYPICAL TEMPORARY
ENABLING WORKS
COMPOUND**



PLAN
SCALE 1:200

NOTES

1. DO NOT SCALE FROM THIS DRAWING.
2. SIZE, NUMBER AND LOCATION OF COMPOUND EQUIPMENT AND FACILITIES ARE INDICATIVE ONLY AND SUBJECT TO CHANGE TO SUIT SITE CONDITIONS.
3. COMPOUND HARDSTAND TO BE REMOVED FOLLOWING CONSTRUCTION WORKS BEING COMPLETED AND GROUND REINSTATED TO ORIGINAL CONDITION.
4. APPROPRIATE MEASURES FOR SEPARATION OF OILS AND TREATMENT OF FOUL WATER TO BE AGREED WITH THE RELEVANT AUTHORITIES
5. VEHICULAR GATES TO BE 6m WIDE CONSISTING OF 2 x 3m LEAVES.
6. COMPOUND HARDSTAND TO CONSIST OF COMPACTED STONE OVER A LAYER OF GEOTEXTILE TO PROVIDE A CLEAN, FIRM, LEVEL AND FREE DRAINING SURFACE SUITABLE FOR CABINS/HEAVY TRAFFIC.
7. FOLLOWING MOBILISATION OF THE MAIN CONSTRUCTION COMPOUND, ALL STRUCTURES, WITH EXCEPTION OF THE GATE HOUSE OFFICE, SHALL BE REMOVED AND THE HARDSTAND AREA WILL BE USED AS A TEMPORARY CAR PARK FOR CONTRACTORS STAFF.

LAYOUT DWG	N/A	T-LAYOUT NO.	N/A
------------	-----	--------------	-----

DRAWING NUMBER	04726-RES-CTN-DR-CO-002	REV	1
----------------	-------------------------	-----	---

SCALE - AS SHOWN @ A3

**ENVIRONMENTAL IMPACT
ASSESSMENT REPORT 2023**

THIS DRAWING IS THE PROPERTY OF RENEWABLE ENERGY SYSTEMS LTD. AND NO REPRODUCTION MAY BE MADE IN WHOLE OR IN PART WITHOUT PERMISSION